BID PROPOSAL

GRAFF STREET STORM SEWER REPLACEMENT
EVERSON BOROUGH

DATE: AUGUST 24, 2026

BID QUOTE INFORMATION

ITEM 1 – 8" HDPE N-12 ST STORM SEWER (LUMP SUM)

a. The Contractor shall furnish and install 8" HDPE N-12 ST storm sewer pipe through open trench excavation, providing all labor, equipment, and materials, including unclassified excavation, saw cutting, asphalt removal, and AASHTO #57 limestone bedding necessary for installation.

b. Sewer pipe installation shall be for all depths of unclassified excavation.

c. Pipe bedding shall consist of AASHTO #57 limestone.

d. Backfill shall be 100% compacted 2A limestone and shall extend from the top of the pipe zone to the asphalt subbase.

e. Temporary cold patch restoration of ditch lines shall be provided, as required.

f. The Contractor shall perform trench dewatering, as necessary, to maintain proper excavation and installation conditions.

g. The Contractor shall contact PA One Call prior to the start of any excavation.

h. The Contractor shall coordinate all construction activities with Everson Borough and emergency service providers. Everson Borough will be responsible for establishing and maintaining the roadway closure and associated traffic control signage between Jones Street/Graff Street and King Street/Graff Street. Access shall be maintained for residents and local property owners within the closure limits. The Contractor shall comply with all traffic control requirements and restrictions established by the Borough.

i. The Contractor shall notify emergency services (EMS) prior to implementing any traffic control or roadway restriction.

j. Lawn restoration shall include placement of 4 inches of topsoil, seeding, and mulching of disturbed lawn areas.

k. The Contractor shall notify & coordinate work with all utility owners.

l. Daily cleanup of waste materials, debris, and rubbish shall be performed.

m. Construction activities shall be limited to the hours of **7:00 AM to 7:00 PM**.

n. Finished surfaces shall match existing grades.

o. The Contractor shall provide temporary sanitary facilities for all jobsite personnel.

p. Waste materials, debris, and rubbish shall be disposed of properly, and the site shall be maintained in a clean and orderly condition at all times.

q. Access to public facilities, businesses, and private residential properties shall be maintained at all times.

r. Unclassified excavation, removal, and disposal of excess excavated material at a permitted site secured by the contractor shall be included.

s. Removal & replacement of the existing concrete invert shall be provided for all piping connections.

t. R-6 limestone riprap and geotextile fabric shall be installed at the existing discharge.

u. Insure requirements: workers composition- statutory amount. Bodily injury- each accident/ each employee $500,000.00: general aggregate – each accordance $2,000,000.00; automotive- each person/ each accident $500,000.00; excess liability- general aggregate $2,000,000.00.

v. All pipe materials shall be supplied from a PennDOT approved supplier. Contractor shall provide written documentation that the supplier is PennDOT approved.

ITEM 2 – ASPHALT RESTORATION (LUMP SUM)

a. Provide asphalt restoration including tack coat, proper compaction, 25 mm Superpave Asphalt Base Course, 9.5 mm Wearing Course, and sealing of asphalt edges.

b. The Contractor shall inspect trenches daily that have been temporarily restored with 2A limestone and make necessary repairs.

c. If asphalt trenches are not permanently restored with hot mix asphalt within five (5) days of the storm sewer installation, a 4-inch-thick cold patch shall be installed. Daily trench inspection & repairs are required until hot mix restoration is completed.

d. Temporary restoration of the driving surface shall be provided at no cost to the Owner until permanent hot mix asphalt restoration is completed.

e. Asphalt materials and installation shall conform to PennDOT Publication 408 standards

---

ITEM 3 – UTILITY TEST PIT EXCAVATION AND BACKFILL (EACH)

Test Pit Excavation – Utility Investigation

a. This item shall be measured and paid as a unit for each utility crossing of the proposed storm sewer and shall include all labor, equipment, and materials necessary to complete the work, including unclassified excavation, shoring, 2A limestone backfill in paved areas, suitable backfill in lawn areas, compaction, utility and property owner coordination, lawn restoration, and temporary asphalt for all roadway crossings.

b. Any downtime associated with utility coordination shall be considered incidental to the project, and no additional compensation shall be allowed.

BID SUBMISSION INFORMATION

Drawing titled "Graff Street Storm Sewer Replacement" Dated 08-12-2026
3 pages total (Cover, Plan, & Detail) are attached as attachments to this bid proposal.

BID DUE DATE: September 14st, 2026
TIME: 6:00 pm
DELIVER BID TO: 232 Brown Street
Deposit bids in the black mailbox labeled **"BOROUGH USE ONLY - NOT FOR USPS"**

No.	Description	Est. Qnty.	Unit	Unit Price ($/Unit)	Bid Amount
1	8” HDPE N-12-ST Storm Sewer	1	Lump Sum		
2	Asphalt Restoration	1	Lump sum		
3	Utility Test Pit Exploratory Excavation & Backfill	3	Each		
TOTAL- WRITTEN QUOTE					**$**

BID CONDITIONS AND ACKNOWLEDGEMENTS

1. **Unit Prices and Quantities**
   Bidder acknowledges that all unit prices include labor, materials, equipment, overhead, and profit. Quantities shown are estimates only and are provided for comparison purposes. Final payment shall be based on actual quantities installed.
2. **Right to Reject**
   The Owner reserves the right to reject any or all bids.
3. **Time of Completion**
   Bidder agrees to complete the Work within 60 days of written authorization of the Borough. Liquidated damages $500.00/days.
4. **Bid Acceptance Period**
   This bid shall remain valid for a period of sixty (60) days from the bid date unless otherwise agreed to in writing.
5. **Site Visit Bid Acceptance Period**
   bidder has visited the site & has reviewed the proposed area prior to submitting of his bid quote.
6. **Documents and Site Conditions**
   Bidder acknowledges review of the bid documents and Addenda (if any), familiarity with the Site and surrounding conditions, and understanding of applicable laws, regulations, and utility coordination requirements.
7. **Addenda**
   Bidder acknowledges receipt of the following Addenda, if applicable:

Addendum Number	Addendum Date

8. **Prevailing wage**
   The engineers estimate is below $25,000, therefore prevailing wages do not apply to this project.

9. **Certifications**
   Bidder certifies that this bid is made in good faith, is not collusive, and has not been influenced by any improper or unlawful conduct.

BID SUBMISSION

The undersigned hereby submits this Bid in accordance with the bid documents and conditions.

Bidder: _____
(Company Name)

Authorized Signature: _____

Name & Title: _____

Date: _____

Contact Information

Contact Name: _____
Title: _____
Phone: _____
Email: _____
Address: _____

Contractor License No. (if applicable): _____